













COLUMN REINFORCEMENT	COLUMN SHAPE	COLUMN REINFORCEMENT	COLUMN SHAPE	COLUMN REINFORCEMENT	COLUMN SHAPE	COLUMN REINFORCEMENT	COLUMN SHAPE	
								ROOF LOWEST LEV.
								2950
								TOP MOST FL. LEV. (14/19TH STY.)
								2900 PER FLOOR
								TYP. STY. FL. LEV.
								2900 PER FLOOR
28H16 H10–100 5XH10–100 10H28(s)		19PC32/19PC32z/14PC32 30H16 2XH10–100 4XH10–100 C 8H28(s)	PC1 14H16 H10–100 2XH10–100 C 8H28(s)	30H16 2XH10–100 4XH10–100 C		30H16 2XH10–100 5XH10–100 10H28(s)		12TH STY. FL. LEV.
	PRECAST 1 TIER EACH		PRECAST 1 TIER EACH				PRECAST 1 TIER EACH	2800
								11TH STY. FL. LEV.
								2800
								10TH STY. FL. LEV.
								2800
								9TH STY. ABOVE
								2800
								8TH STY. FL. LEV.
					CAST IN-SITU			2800
28H20 H10–100 5XH10–100 10H28(s)		19PC32/19PC32z/14PC32 30H20 2XH10–100 4XH10–100 C 8H28(s)	PC1 14H20 H10–100 2XH10–100 C 8H28(s)	30H20 2XH10–100 4XH10–100 C		30H20 2XH10–100 5XH10–100 10H28(s)		7TH STY. FL. LEV.
								2800
								6TH STY. FL. LEV.
								2800
								5TH STY. FL. LEV.
								2800
								4TH STY. FL. LEV.
								2800
28H25 H13–100 5XH10–100 10H28(s)		19PC32/19PC32z/14PC32 30H25 2XH13–100 4XH10–100 C 8H28(s) PC1 14H25 H13–100 2XH10–100 C 8H28(s)				30H25 2XH13–100 5XH10–100 10H28(s)		3RD STY. FL. LEV.
								2800
								2ND STY. FL. LEV.
28H28 H13–100 5XH10–100 * DOWELS		2XH32–150(V) 2X2H13–100(H) * DOWELS		30H28 2XH13–100 4XH10–100 C		30H28 2XH13–100 5XH10–100 * DOWELS		SEE ARCH
	CAST IN-SITU		CAST IN-SITU				CAST IN-SITU	1ST STY. FL. LEV.
28H28 H13–100 5XH10–100		2XH32–150(V) 2X2H13–100(H)		30H28 2XH13–100 4XH10–100 C		30H28 2XH13–100 5XH10–100		SEE ARCH
								FOUNDATION BASE
19PC31z/14PC31		19PC32z/14PC32		19C33z/14C33		19PC34z/14PC34		COLUMN MARKING

TYPICAL POSITION OF SPLICE BAR FOR COLUMNS AND WALLS (SCALE 1:40)



SHOWING LINK REQUIREMENT AT SPLICE SLEEVE (FOR PRECAST COLUMN) (SCALE 1:40)

NOTES : * H8 FOR TYPICAL STOREY, H10 FOR 1ST STOREY.



TENDER DRAWING

HOUSING & DEVELOPMENT BOARD
HDB Hub 480 Lorong 6 Toa Payoh
Singapore 310480

OWNER SIGNATURE:

DRAWING NO. HB–D2509–CS– D01	REVISION: –
PRECINCT NAME: –	BTO

PROJECT TITLE
BUILDING WORKS AT PROJECT DT (TOTAL: 193 DWELLING UNITS)

LOT NO.: –	MUKIM NO.: –

JOB TITLE
PROJECT DT

DRAWING TITLE (EST. BLK. 321A & 321B)


COLUMN SCHEDULE

PART 1

SCALE: 1:60	DATE: JAN 2026
DRAWN BY: WANG JING	CHECKED BY: LIM MUI SIOK

NOTES:

1. THE COLUMN STUMP SIZE AT FOUNDATION SHALL BE ENLARGED BY 100mm ON EACH SIDE IN THE SHORTER DIRECTION AS SHOWN UNLESS OTHERWISE DETAILED IN PILECAP PLAN.
2. FOR COLUMNS CARRYING WATER TANK STUMP, SPLICE BARS TO BE PROVIDED AT ROOF WHERE REQUIRED BY STUMPS/FASCIA STUMPS TO REFER TO WATER TANK ROOM/ LIFT MACHINE ROOM/ROOF ELEMENT DRAWINGS. SIZE AND NO. OF DOWEL BAR SHALL BE THE SAME AS WATER TANK STUMP DETAILS.
3. SIZE AND ACTUAL LOCATION OF WET POUR, 'BOX OUT PORTION', PROVISION OF RECESS AND ADDITIONAL LINKS IN PRECAST COLUMN NOT SHOWN TO BE READ IN CONJUNCTION WITH TYPICAL STOREY BEAM AND PRECAST FACADE LAYOUT PLAN. FOR CONNECTION AND WATER PROOFING DETAILS TO REFER TO STRUCTURAL STANDARD DRAWINGS.
4. 's' & 'p' DENOTES APPROVED SPLICING SYSTEM WITH REBARS. DETAILS REFER TO PRECAST COLUMN REFERENCE DETAILS.
5. NOS AND SIZES OF APPROVED SPLICING SYSTEM WILL ONLY BE INDICATED AT THE COLUMN SCHEDULE UNLESS OTHERWISE SPECIFIED. FOR EXAMPLE:




THE PROVISION OF APPROVED SPLICING SYSTEM AS SHOWN IN THE COLUMN SCHEDULE IS APPLICABLE TO ALL CONNECTION LEVELS OF THE PRECAST COLUMNS.

6. DETAILS OF COLUMN DOWEL BARS AND LINKS NOT SHOWN TO REFER TO "TYPICAL COLUMN SPLICE LENGTH AND LINK SPACING TABLE" IN STRUCTURAL STANDARD DRAWINGS.
7. * DOWEL BARS (OF SAME DIAMETER) TO BE PROVIDED WHERE APPLICABLE.
8. FINS TO BE PROVIDED WHERE APPLICABLE. ACTUAL SIZE AND LOCATION OF FINS TO REFER TO INDIVIDUAL FLOOR PLANS AND TO BE CONFIRMED WITH ARCH. DWGS PRIOR CASTING. AND DETAILS NOT SHOWN TO REFER TO STRUCTUAL STANDARD DRAWINGS UNLESS OTHERWISE DETAILED IN COLUMN REFERENCE DETAILS.
9. COLUMN DETAILS SHALL BE READ IN CONJUNCTION WITH PRECAST COLUMN/ WALL REFERENCE DETAILS.
10. COLUMN MARKING WITH * SHALL BE READ IN CONJUNCTION WITH PRECAST FACADE & PRECAST GABLE END WALL DRAWINGS.
11. PROVISON OF CONCEALED WATER PIPES TO REFER TO "TYPICAL DETAILS SHOWING CONCEALED SERVICE PIPES ABUTTING TO COLUMN / WALL / BEAM AND PROVISION OF OPENINGS FOR HOT WATER PIPES".
12. LOCATION OF GROUT TUBE NOT SHOWN TO REFER TO STRUCTURAL STANDARD DRAWINGS.
13. DIMENSIONS WITH '*' TO BE CONFIRMED WITH ARCH. DWGS.
14. PRECAST FACADE CONSTRUCTION JOINTS ARE TO BE CONSTRUCTED TO CS DETAILS. SHOULD GROOVE LINES BE REQUIRED AT PRESSURE GROUTED AREAS. THE DEPTH OF THE GROOVE LINES SHALL NOT EXCEED THE THICKNESS OF THE SKIM COAT AND SHALL NOT CUT INTO NOR REDUCE THE PRESSURE GROUTED JOINT.

COLUMN WIDTH AT FOUNDATION AND 1ST STOREY

1. COLUMN WIDTH AT FOUNDATION AND 1ST STOREY SHALL BE MIN. 300mm.



AMENDMENT	DATE	DRAWN BY	CHECKED BY	DESIGN ENGR.	QP

AMENDMENT	DATE	DRAWN BY	CHECKED BY	DESIGN ENGR.	QP

AMENDMENT	DATE	DRAWN BY	CHECKED BY	DESIGN ENGR.	QP

REFERENCE :

Surbana Jurong Consultants Pte. Ltd.
Surbana Jurong Campus, 38 Cleantech Loop, #01-31, Singapore 636741
Tel: +65 62481288
www.surbanajurong.com
Company Regn No: 200304951Z

DRAWING NO. SB–DP–HABI–D2412–CS– D01	REVISION: –
LIM TAU TZONG DESIGN ENGINEER	Er. TENG CHEE WAI QUALIFIED PERSON

THE OWNERSHIP OF THE COPYRIGHT IN THIS DRAWING IS RETAINED BY SURBANA JURONG CONSULTANTS PTE LTD WHOSE CONSENT MUST BE SOUGHT BEFORE ANY USE OR REPRODUCTION OF THE DRAWING OR ANY PART THEREOF CAN BE MADE.